

DORIS

DAYS
2021

November 16,17 and 18

Ground stations components

Jérôme Saunier (IGN)



November 18
Session 3 – Presentation 5

Ground station components

The beacon

generates two modulated signals: 401.25MHz / 2036.25MHz
contains the reference oscillator, the frequency synthesizer,
and the management board

The remote control system

allows basic settings and adjustments from the Control Center

The power pack

supplies power and charges the battery

The battery

supplies power in case of mains failure

The antenna

transmits the signal generated by the beacon

The cables

keep every component connected

Indoor equipment




Hardware development (1/2)


- **4 generations of beacons (transmitter)**
- **1990-1995-2001-2019:** 4 generations of beacons have been developed improving each time reliability, robustness and performance
 - **4th generation beacon deployment began in June 2019** => see *C. Manfredi (CNES) presentation 6*
- **Current network equipment:** 40 stations equipped with 3rd generation/19 with 4th generation beacon



1.0



2.0



3.0





4.0

Hardware development (2/2)

- **3 generations of antennae**

- **1992-2006:** gradual replacement of Alcatel antennae with Starec antennae
- **Different design:** compact / helical antenna and **better DORIS measurement accuracy**
- **2014: key development: Antenna C type:** same design as Starec B but with consolidated specifications: the uncertainty of the vertical location of the 2GHz phase center is reduced from 5 mm to 2 mm



Equipment requirements

1. Continuous service 24/7 365 days operation

a.Mains


- Continuous feed and power stability is required to generate and transmit the DORIS signal

b.Signal transmission

- Deliberate or automatic switch to stand-by mode are prohibited
- Possible interferences with other nearby equipment must be considered before installation

c.Troubleshooting

- Site accessibility and fast customs clearance are necessary for the shipping of spare equipment



1a. Mains



Power supply / EX. I_80: Maximum duration of power failures ≤ 1 hour

Power supply / EX. I_90: Maximum frequency of power failures = 1 per day

Power supply / EX. I_270: Monthly total of power failures < 6 hours

Power supply / EX. I_100: Electric current characteristics: 100 VAC to 264 VAC voltage

Power supply / EX. I_110: Mains frequency 48 to 66 Hz

Power supply / EX. I_260: Minimum rating of the circuit-breaker/fuse on the power supply line equal to at least 10 amps

⇒ In most cases, domestic electricity mains supply complies with these requirements. In difficult areas, uninterrupted power supply (UPS) system or backup power is required

⇒ The maximum operating life of the DORIS battery is two hours

⇒ Beacon power consumption: 130 Wh

⇒ Note that the DORIS system does not require any connectivity for data transmission

1b. Signal transmission



Signal transmission/ EX. I_50: Sites requiring a deliberate switch to stand-by are prohibited

Signal transmission/ EX. I_60: The use of a timer for automatic switch to stand-by is prohibited

Signal transmission/ EX. I_70: A transmission authorization from the cognizant authority in the host country is mandatory prior to installation of the equipment on site

Signal transmission/ EX. F_181: The characteristics of each radiofrequency system on the station site shall be listed : frequencies used, emitting/receiving, permanently/episodically, power

Signal transmission/ EX. F_182: Before installation, radiofrequency interferences with other systems shall be managed

⇒ **During radiosonde balloon launches or VLBI observations, inhibiting DORIS transmission from the beacon using the stand-by mode is no longer granted because of:**

- Difficulties in managing the network (one-way switch, return to transmission overlooked...)
- Incurred measurement losses that reduce the station performance

⇒ **Possible RF interferences with nearby equipment must be examined prior installation and on a regular basis afterwards to prevent problems**

- In any case, radiofrequency authorization from local Authority must be granted or renewed

1c. Troubleshooting



Maintenance / EX. F_160: In case of failure, the replacement beacon must be configured so as to have exactly the same number and the same hexadecimal code as the faulty equipment

Maintenance / EX. I_30: Presence on site (i.e. less than 30 minutes away from the beacon) of personnel qualified to carry out standard maintenance operations on DORIS stations is required

Maintenance/ EX. I_40: The dispatch of equipment must be possible at least every two months, with customs clearance time shorter than two months

⇒ Quick troubleshooting is essential to ensure a good data availability

⇒ Time for fault diagnosis, equipment shipping, customs clearance, and equipment replacement should be minimized



Equipment requirements

2. Installation specifications

a. Equipment housing

- Dedicated shelter or room or space for the indoor equipment

b. Beacon environment

- Suitable operating conditions: temperatures, no corrosive environment...

c. Cables routing


- No tension forces on cables and connectors

2a. Equipment housing



Beacon room / EX. I_295: The room where the beacon is to be stored must present cleanliness conditions (no excessive amount of dust, no animal droppings...)

- ⇒ to accommodate the indoor equipment, 2 square meters facility is enough
- ⇒ a standard 19" equipment rack is provided by CNES
- ⇒ a dedicated shelter might be the best option



2b. Beacon environment



Beacon room / EX. I_120: The operating temperature range must be between 0°C and 45°C with maximum gradient 10°C/hour inside the beacon room

Beacon room / EX. I_370: No DORIS beacon shall be installed in a place subjected to vibrations (OUS and electronic unit vibrations)

Beacon room / EX. I_295: Avoid too much corrosive moods as much as possible

⇒ **Air conditioning system is recommended to regulate temperature and avoid moisture**

⇒ **Avoid place where people are constantly coming and going (dedicated room or shelter is better)**

2c. Cables routing

Cables / EX. I_210: The use of right-angled adapters is prohibited at the antenna bottom and the beacon rear panel

Cables / EX. I_220: The cables bend radius must be greater than 20 cm (margins in relation to 12.5 centimeters in the beacon specification of requirement)

Cables / EX. I_230: Cable length = 15 meters for sites fitted out with a 3.0 or 3.1 beacon.
Cable length = 25 or 50 meters for sites fitted out with a 4.0 beacon.

Cables / EX. I_320: The preforming of cables and their fastening on the antenna support must be such that the connectors can be screwed and unscrewed by hand, with no need for a tool.

Cables / EX. I_330: The cables must be mechanically fastened to the antenna support, as close as possible to the connectors, without applying any stress.

⇒ **Ensuring that no stresses, no tension forces are exerted on the cables or the connectors due to improper installation or external cause (wind, hanging...)**

⇒ **Cable trays or buried cable ducts are recommended**

Equipment requirements in summary

- Continuous service and reliable power supply
- Continuous signal transmission (least possible amount of downtime)
- Fastest possible troubleshooting
- Dry, clean and quiet room to ensure smooth operation of the beacon
- Reasonable temperature variations inside the room
- Particular attention to the cables routing to avoid signal disruption