

# The D O R I S network

- ➔ **Antenna stability improvement: status and prospective**
- ➔ **The 3.0 beacons:**
  - New features
  - Improvement of the reliability
- ➔ **Beacons disposability: 2.0 and 3.0 models**
- ➔ **Other possible improvements:**
  - Reducing the time between failure and replacement
  - Uniform model of antenna over the network
- ➔ **Information and formalization of the relations with the host institutes**



# Antenna stability

**Currently 3 different options:**

➔ **Pillar on ground floor:**

Represent 15 sites among the renovated or newly installed sites since 1999.

➔ **Rigid metal tower 2 meters high on ground or stable building structure: 6 sites since 1999.**

➔ **Rigid metal tower 1 meter high or less on building structure: 3 sites since 1999.**



# Types of supports

Concrete pillar



2m tower on concrete structure



Short tower on building



# Status and prospective

- ➔ **Configuration adopted for the moment**
  - Metal corrosion problems seem to be solved
  - Long term resistance should be achieved
- ➔ **Further improvements**
  - Concrete structure stability in case of soil ground
  - Initial study including ground structure when installing a new site
  - Cross comparison with other techniques?
- ➔ **Positive results at half way of this process**
- ➔ **Some difficult sites to prospect from now on**
- ➔ **The whole network equipped with STAREC antennas:  
better phase center determination relatively to a materialized point.**



## 3.0 beacons: installation process

### ➔ Installation process beginning

- 2 beacons installed (Toulouse, Tristan da Cunha)
- 4 beacons more installed within 2 months
- 5 beacons delivered in June 2002 to SIMB
- 15 beacons/year delivery planned for the coming years

### ➔ Master beacon function operational in Toulouse

- Automatic uploads for satellites programming soon achieved
- Network image uploaded now to the 2nd generation receivers




## 3.0 beacons: new features

- ➔ **Modulation of the signal on the 2 GHz frequency**
  - Same message as 400 MHz
  - Allows eventual mono-frequency receivers conception
  - Measurements available even if 400 MHz interference
  
- ➔ **More control values transmitted**
  - Internal temperature
  - Transmitted power out of the amplifiers
  - Date and time (modulo 10 seconds)
  - Time elapsed since oscillator was on
  - Indicator of restart mode



# Beacons clock lag determination




**Master beacon connected  
with cesium controlled by  
CNES time /frequency  
laboratory**

**Transmitting  
beacon**

- Beacons time controlled through the system to TAI, but modulo 10 seconds.
- Time lag between beacon time and TAI known after beacon reception and data treatment

# Constraint for beacon's time setting (1.0 and 2.0 beacons)




A time lag of around 5 seconds when setting beacon's time doesn't allow reception of the modulation on the satellites. The measurements are lost in this case.





# Restart mode with 3.0 beacons



## Restart mode allows 2 new features:

- automatic restart of the beacon in transmission mode after a cut off
- possibility to receive measurements with any time lag

Restart mode is the default mode when switching on the beacon.



## Beacons 3.0: other new features

- ➔ **Frequency lag programming available**
  - Avoid Doppler conflicts for beacons close together
  - Useful for the new 2 channels receivers
- ➔ **External power supply system**
  - 3 different sets of battery: adaptability to diverse configurations
  - Large voltage and frequency variability accepted
- ➔ **Possibility of remote control in the near future: useful for remote sites and non permanently maintained**
- ➔ **New generation of oscillators: stability increased by a factor 3 relatively to 1.0 beacons**



# Beacon's availability

- ➔ **1.0 beacons replaced by the 3.0 and no more used**
  - Many components not constructed anymore
  - Difficult to maintain these beacons
- ➔ **2.0 beacons**
  - 26 existing —> allow 20 operational
  - Reliability increased since a protection module against signal return to the amplifiers implemented on 2 GHz output
  - Study initiated for 3.0 synthesizer implementation in 2.0 beacons ( —> 2.1 model? )
- ➔ **3.0 beacons**
  - Regular delivery quite sure as all initial problems seem to be solved
  - Only USO delivery could limit delivery



# Other possible improvements

- ➔ **Improve the sites measurement continuity**
  - Time sometimes important between failure and installation of a new beacon
    - › mostly due to customs procedures
  - Failure determination only through communications
    - › partial information or misunderstanding can lead to long time before diagnosis (even more important problem for temporary experiments)
- ➔ **Possible actions:**
  - Try to ameliorate communications
  - Improve the equipment reliability: objective during the 3.0 conception
- ➔ **Improve meteorological measurements reliability: regular calibrations or comparisons to perform**



# Host Institutes and SIMB relations

- ➔ **Agreements signed between IGN and host institutes**
  - Facilitates administrative problems resolution
  - Gives an official status to the relations
  - Gives a base of discussion when problems arise
- ➔ **Information about the DORIS system and results**
  - Available through IDS web site
  - Altimetry data and information available on AVISO web site

