



# **DORIS NETWORK STATUS**

#### 30 YEARS AFTER THE START OF THE NETWORK DEPLOYMENT

**JEROME SAUNIER, IGN - FRANCE** 





# NETWORK DEPLOYMENT AND EVOLUTION D



#### 1986-1992: SETTING-UP

- First station installed at Tristan da Cunha in June 1986
- 32 stations for the launch of Spot-2 = start of the system
- 47 stations at the end of 1992

#### 1993-1999: DENSIFICATION

- Coverage improvement (several stations moved)
- Start of the Starec antenna (93); second generation beacon (95)
- 54 stations at the end of 1999

#### 2000-2009: RENOVATION

- Objective: improvement of the stability and the environment of the antenna
- Antenna support changes and often, relocating

#### 2010-TODAY: MODERNIZATION


- Permanent monitoring: "DORIS integrity workshop" (2010)
- Standardization: "sites standard configuration" (2013)
- Performance assessment: "assessment of the DORIS network monumentation" (2015)
- 4<sup>th</sup> generation beacon under preparation (2019: initial deployment)



## **NETWORK EVOLUTION**



### NUMBER OF STATIONS OF THE PERMANENT NETWORK






## **NETWORK DISTRIBUTION**



- VERY HOMOGENEOUS GEOGRAPHICAL DISTRIBUTION
  - Coverage gap in Pacific due the decommissioning of Sakhalinsk and Port-Moresby



Sentinel-3 coverage (cut-off angle: 12°)



# **NETWORK MONUMENTATION**



### 3 STANDARD MONUMENTS



Type I (16%): short antenna support on load-bearing wall of a small building



Type II (24%): custommade tripod on concrete pillar




Type III (22%): very rigid steel tower on concrete block

- Elastic deformations < 1 mm when undergoing extreme climatic conditions</p>
- 50 verticality checks in the last 15 y. : 80% of the monuments are stable (within a mm)
- 2/3 of the network monuments are compliant with standards
- Further details: "Assessment of the DORIS network monumentation": 10.1016/j.asr.2016.02.026

## STABILITY ASSESSEMENT




### QUALITATIVE ANALYSIS OF THE NETWORK MONUMENTATION



## **OPERATIONNAL STATUS**



#### 59 stations of which: 9 beacons are out of order (4 decommissioned)




Yuzhno-Sakhalinsk (11/2005), Santa Cruz (06/2009), Santiago (05/2013), Port-Moresby (06/2013)



### **NETWORK AVAILABILITY**



- 5 MAINTENANCE OPERATIONS SINCE THE BEGINNING OF 2016
- MAINTAINED OVER 85% OF OPERATING STATIONS SINCE 2012






## **NETWORK RELIABILITY**



#### OPERATING TIME OF THE CURRENT STATIONS


Average: 21 years / Median: 24 years



# **NETWORK PERFORMANCE**



#### DORIS network activity from January 1993



From IDS CC Data (ids12: 1993003 => 2015354)

# **NETWORK EVENTS (1/3)**



| 2014     |                          |                                  |  |  |  |  |
|----------|--------------------------|----------------------------------|--|--|--|--|
| November | COBB                     | Cold Bay                         | Beacon replacement   |  |  |  |
|          | OWEC                     | Owenga                           | New site in place of Chatham   |  |  |  |
| December |                          | Wettzell                         | Reconnaissance with a view to install a new station                    |  |  |  |
| 2015     |                          |                                  |  |  |  |  |
| January  | ROW<br>C<br>KEUC<br>CIDB | Rothera<br>Kerguelen<br>Cibinong | Antenna replacement Antenna replacement Beacon replacement             |  |  |  |
| March    | ADHC<br>GONC             | Terre Adélie<br>Goldstone        | Antenna replacement  New site in place of Monument Peak                |  |  |  |
| April    | TLSB<br>ADHC             | Toulouse<br>Terre Adélie         | Beacon & Tracking oscillator replacement Time beacon back to operation |  |  |  |
| May      | KRWB                     | Kourou                           | Tracking oscillator replacement  |  |  |  |

<u>In italics</u>: operational maintenance (equipment replacement) carried out by CNES with the participation of Host Agencies

In normal font: on-site operations carried out by IGN

In bold: main events

# **NETWORK EVENTS (2/3)**



# 2015

| June     | -        | Japan          | Abandoned after failed negotiation on frequency clearance |
|----------|----------|----------------|---|
| July     | -        | N. Australia   | Reconnaissance with a view to installing a new station    |
|          | KRWB     | Kourou         | Tracking oscillator replacement                           |
| August   | EASB     | Easter Island  | Station removed   |
|          | HBMB     | Hartebeesthoek | Beacon replacement  |
|          | SPJB     | Ny-Ålesund     | Reconnaissance with a view to relocating the station      |
| October  | JIUB     | Jiufeng        | Antenna replacement                                       |
|          | SAPC     | Sal            | Antenna re-location (shift of 5 m)                        |
| November | CADB     | Cachoiera      | Beacon replacement  |
|          | OWE<br>C | Owenga         | Beacon replacement  |
| December | PDOC     | Ponta Delgada  | Equipment replacement (antenna + beacon)                  |
|          | AMW<br>B | Amsterdam      | Beacon replacement  |
|          | KRBB     | Krasnoyarsk    | Beacon replacement  |

# **NETWORK EVENTS (3/3)**



| 2016      |              |                                   |   |  |  |
|-----------|--------------|-----------------------------------|---|--|--|
| January   | CIDB         | Cibinong                          | Beacon replacement  |  |  |
| Febuary   | MIAB         | Miami                             | Beacon replacement  |  |  |
| March     | HBMB<br>OWFC | Hartebeesthoek  Owenga            | Tracking oscillator replacement  Station re-location (80m North-West)   |  |  |
| April     | MNAC         | Managua                           | New site  |  |  |
| May       | TRJB<br>-    | Tristan da Cunha  Mariana Islands | Beacon replacement Reconnaissance with a view to installing new station |  |  |
| June      | KIVC         | Kitab                             | Station re-location (200m South)  |  |  |
| July      | ASEB<br>STKB | Ascension<br>St-John's            | Beacon replacement  Beacon replacement                                  |  |  |
| August    | CACB         | Cachoeira Paulista                | Beacon replacement  |  |  |
| September | HBMB<br>WEUC | Hartebeesthoek Wettzell           | Tracking oscillator replacement  New site (IDS station)                 |  |  |

## **NETWORK EVOLUTION**



#### PLANNED NEXT YEAR

- Santiago, CHL: station re-location in Argentina, San Juan (SLR+GNSS)
- Easter Island, CHL: station re-location following site closure in 2015
- Guam, Mariana Islands, USA: new site (co-location GNSS + tide gauge)

#### UNDER PLANNING

- Port-Moresby, PNG: station re-location in Australia, Katherine (GNSS+VLBI)
- Ny-Ålesund, NOR: station re-location 3 km away (co-location GNSS+SLR+VLBI)

#### UNDER CONSIDERATION

- Northern Asia: new site in place of Yuzhno in Manchuria (CHN)
- Reykjavik, ISL: station re-location to get better performance
- Tahiti, French Polynesia: new 4 techniques site project

## **FUTURE DEVELOPMENTS**



### 4<sup>TH</sup> GENERATION BEACON

- New electronic components; new architecture
- Antenna cables allowing to install it up to 50m from the beacon
- Initial deployment could start in 2019

#### MONUMENT STABILITY MONITORING

- Grasse: experimental site
- Equipping sites with control points and targets to carry out stability monitoring surveys
- Installing devices such as tiltmeter or Geocube (small GPS receiver)

#### DORIS / VLBI RF COMPATIBILITY

Investigation for RF blockers or absorbers